

**CITY OF YORBA LINDA PUBLIC WORKS DEPARTMENT  
EROSION AND SEDIMENT CONTROL NOTES**

1. IN CASE OF EMERGENCY CALL \_\_\_\_\_ AT \_\_\_\_\_  
(RESPONSIBLE PERSON) (24-HR PHONE NUMBER)

\_\_\_\_\_  
(TITLE AND COMPANY)

2. THE UNDERSIGNED CIVIL ENGINEER WILL REVIEW EROSION AND SEDIMENT CONTROL WORK AND CERTIFY THAT WORK IS IN ACCORDANCE WITH THE ACCEPTED PLAN AND STORM WATER POLLUTION PREVENTION PLAN (SWPPP).
3. A STANDBY CREW FOR EMERGENCY WORK SHALL BE AVAILABLE AT ALL TIMES DURING THE RAINY SEASON. NECESSARY MATERIALS SHALL BE AVAILABLE ON SITE AND STOCKPILED AT CONVENIENT LOCATIONS TO FACILITATE RAPID CONSTRUCTION OF TEMPORARY BEST MANAGEMENT PRACTICES (BMPS) OR TO REPAIR ANY DAMAGED EROSION AND SEDIMENT CONTROL MEASURES WHEN RAIN IS IMMINENT.
4. BMPS SHALL NOT BE MOVED OR MODIFIED WITHOUT THE DIRECTION OF THE QUALIFIED SWPPP DEVELOPER (QSD) OR QUALIFIED SWPPP PRACTITIONER (QSP).
5. ALL REMOVABLE PROTECTIVE BMPS SHOWN SHALL BE IN PLACE AT THE END OF EACH WORKING DAY WHEN RAIN IS IMMINENT. PERIMETER AND TRACKING BMPS SHALL BE IN PLACE AT ALL TIMES.
6. AFTER A RAINSTORM, ALL SILT AND DEBRIS SHALL BE REMOVED FROM STREETS, CHECK BERMS, AND DESILTING BASINS AND THE BASINS DRAINED WITHIN 24 TO 96 HOURS. ANY GRADED SLOPE SURFACE PROTECTION MEASURES DAMAGED DURING A RAINSTORM SHALL BE IMMEDIATELY REPAIRED.
7. GRADED AREAS ON THE PERIMETER MUST DRAIN AWAY FROM SLOPES AT THE CONCLUSION OF EACH WORKING DAY. DRAINAGE SHALL BE DIRECTED TOWARD DESILTING FACILITIES.
8. A GUARD SHALL BE POSTED ON THE SITE WHENEVER THE DEPTH OF WATER IN A BASIN EXCEEDS TWO FEET.
9. PLACEMENT OF BMPS TO REDUCE EROSION DAMAGE ON THE PROJECT SITE MUST BE SHOWN ON THE PLAN.
10. THE CONTRACTOR SHALL BE RESPONSIBLE AND SHALL TAKE NECESSARY PRECAUTIONS TO PREVENT PUBLIC TRESPASS ONTO AREA WHERE IMPOUNDED WATER CREATES A HAZARDOUS CONDITION.
11. ALL OFFSITE DOWNSTREAM CATCH BASINS SHALL HAVE INLET PROTECTION.
12. ALL PERIMETER BMPS AND STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED PRIOR TO GRADING OR DEMOLITION MOBILIZATION OR OPERATION.
13. SPOIL AND PERMITTED STOCKPILES OF SOIL SHALL BE PROPERLY CONTAINED TO MINIMIZE SEDIMENT TRANSPORT VIA RUNOFF, VEHICLE TRACKING, OR WIND.
14. THE CONTRACTOR SHALL PROVIDE EFFECTIVE SOIL COVER TO THE SATISFACTION OF THE INSPECTOR FOR INACTIVE AREAS THAT ARE DISTURBED AND ARE NOT SCHEDULED TO BE RE-DISTURBED FOR AT LEAST 14 DAYS AND ALL FINISHED SLOPES, OPEN SPACE, UTILITY BACKFILL, AND COMPLETED LOTS.